

Pilot Testing of CO₂ Sparging for a Caustic Groundwater Plume in a Coastal Aquifer

presented by

Lynda Smithard, P.Eng. Stephen Sumsion, B.A.Sc., EIT

McCue Environmental Contracting Inc.





Common method of pH adjustment in WW treatment

Takes advantage of simple chemistry:

 $2NaOH + CO_2 = Na_2CO_3$ (Sodium Carbonate) + H₂O

 $NaOH + CO_2 = Na_2HCO_3$ (Sodium Bicarbonate)

Reaction product is dictated by the water pH



O₂ Sparging Benefits

Handling of acid eliminated

Risk of overdosing acid and associated problems eliminated

Equipment requirements less than other technologies

O&M requirements less than other technologies





Project Site

A portion of the groundwater beneath the chemical plant has pH values in excess of 7.0 (caustic)

High pH plume present in shallow, intermediate and deep groundwater zones corresponding to freshwater, freshwater/saltwater transition and saline zones

High pH plume discharging to marine environment

Client began site investigations in 2001 and continues to investigate and monitor the groundwater and receiving environment conditions

pH Plume Distribution (Shallow: 2-11m bgs)

ENVIRONMENTAL



pH Plume Distribution (Intermediate: 11-21m bgs.)



INVIRONMENTAL





Discharge area defined by direct push sampling

Area of discharge approximately 75 m²

Groundwater discharging from freshwater and saltwater/freshwater transition zones of aquifer

McCUE ONTRACTING DH Plume Discharge Area





GCW Pilot Test

From 2004 to 2006 groundwater circulation well and pump and treat technologies were pilot tested to assess neutralizing the high pH groundwater using hydrochloric acid

GCW technology not viable but the findings led to the 09 CO2 sparging pilot test



Mccue Initial GCW System Design









GCW Troubleshooting

Several start-up issues including equipment scaling

System had to be reconfigured and a new pump installed



MCCUE Contracting

GCW Troubleshooting

Pumping rate observed to decrease over duration of pilot trial

Performed groundwater modeling to predict groundwater treatment zone at the end of the pilot trial



Figure 4. GCW Flow vs. Time





GCW Troubleshooting

Decrease in pumping rate attributed to scale formation

Bench tests using soil and groundwater from transition and saline zones produced a white "gel" precipitate

Results indicated scale formed when treated saline groundwater was injected into untreated saline groundwater





GCW Troubleshooting

Bench tests using soil and groundwater from freshwater zone produced no precipitates

Bench tests suggested scale issues related to pH reduction in saline water





Supplemental Pilot Trial

Re-configured the system in 06 to assess feasibility of intermediate injection point (well hydraulics / fouling / scaling)

Installation of an intermediate injection well above the depth of saline groundwater

Monitored pump rates, water levels and pH in surrounding monitoring wells



Supplemental Pilot Trial – Average Daily Pump Rates



Date



GCW Pilot Test Conclusions

Long term decreases in pH in system monitoring wells indicated the GCW pilot system had a positive effect but low pumping rates significantly decreased the size of the treatment zone

Direct cause of the scale formation could not be determined

Concluded GCW technology was not viable at the site

Column tests suggested treating GW in situ using CO2 may be possible without fouling the wells



Three purpose built sparge wells screened in freshwater, transition and saline zones

Well ID	Screen Interval (mbgs)
SW1S	7.7-8.0
SW1I	16.7-17
SW1D	27.2-27.5

A temporary manifold was designed for the operation of the pilot system





Theoretical breakthrough pressures calculated based on the well construction and monitoring information

Breakthrough pressure is the pressure required to evacuate standing water from the well

Well #	Breakthrough (BT) Pressure (psi)	BT 110% (psi)	BT 125% (psi)	BT 150% (psi)
SW1S	6.7	7.4	8.4	10.1
SW1I	19.1	21.0	23.9	28.7
SW1D	33.1	36.4	41.3	49.6

MCCUE

CONTRACTING

CO₂ Pilot Trial Test Summary

Test #	Test Well ID	Test Description	Date of Test
1	SW1S	@ 110% Breakthrough Pressure	Mar-24
2	SW1S	@ 125% Breakthrough Pressure	Mar-24
3	SW1S	@ 110+% Breakthrough Pressure	Mar-25
4	SW1I	@ Breakthrough Pressure to 150% Breakthrough Pressure	Mar-26
5	SW1I	@ 125% to 150+% Breakthrough Pressure	Mar-27
6	SW1I	@ 125% to <150% Breakthrough Pressure	Mar-30
7	SW1I	@ Breakthrough Pressure	Apr-06
8	SW1D	@ 110% Breakthrough Pressure	Mar-31
9	SW1D	@ Breakthrough Pressure to 125% Breakthrough Pressure	Apr-01
10	Combined - all 3 wells	 @ 125% Breakthrough Pressure / 110% Breakthrough Pressure / 110% Breakthrough Pressure 	Apr-02
11	Combined - all 3 wells	 @ 110% Breakthrough Pressure / Breakthrough Pressure / Breakthrough Pressure 	Apr-07



To monitor for surrounding influence the surrounding sparge wells (during single wells sparge tests) were monitored for headspace pressure, O₂ and CO₂

Surrounding monitoring wells monitored for the above plus: pH, conductivity, ORP, temperature, DO, and salinity

Transducers placed in surrounding monitoring wells







Results

Test well data demonstrated sufficient CO₂ flows achieved

Fugitive CO₂ encountered in sparge wells and nearby wells

As expected, higher flows translated into higher fugitive CO₂





Positive radii of influence observed at 8 m distance from sparge well

Reduction in pH observed 8 m from the sparge well between 15 minutes to 60 minutes from start of test

Observed pH reduction in both shallow and intermediate zones:

-pH decreased from 11.14 to 6.43 in shallow MW (combined test)

-pH decreased from 13.21 to 6.17 in intermediate MW (SW1I test)

-Did not observe pH decrease in deep monitoring well



2 April - All Well Trial









Hydraulic permeability tests determined the hydraulic conductivity for the site to be 1.3×10^{-3} m/s

Permeability testing was conducted before and after the pilot trial to monitor for scaling identified during the GCW pilot test



	Confined (Hvorslev) Hydraulic Conductivity (m/s)		Unconfined (Bouwer & Rice) Hydraulic Conductivity (m/s)	
Well ID	Pre-Test	Post-Test	Pre-Test	Post-Test
MW-27D	4.9 x 10 ⁻⁴	n/a	4.5 x 10 ⁻⁴	n/a
	4.5 x 10 ⁻⁴		4.1 x 10 ⁻⁴	
SW-1S	4.7 x 10 ⁻⁴	n/a	3.8 x 10 ⁻⁴	n/a
	5.4 x 10 ⁻⁴		4.5 x 10 ⁻⁴	
SW-1I	n/a	6.1 x 10 ⁻⁶	n/a	5.6 x 10 ⁻⁵
		5.2 x 10 ⁻⁶		4.8 x 10 ⁻⁵
SW-1D	2.8 x 10 ⁻⁴	3.4 x 10 ⁻⁴	2.7 x 10 ⁻⁴	3.2 x 10 ⁻⁴
	2.3 x 10 ⁻⁴	2.4 x 10 ⁻⁴	2.2 x 10 ⁻⁴	2.3 x 10 ⁻⁴
MW-27S	6.0 x 10 ⁻⁴	3.3 x 10 ⁻⁴	1.6 x 10 ⁻³	8.7 x 10 ⁻⁴
		2.3 x 10 ⁻⁴		6.0 x 10 ⁻⁴





CO₂ sparging demonstrated effective pH buffering

No significant reduction of hydraulic conductivity observed following the completion of the pilot trial

Good radius of influence observed

Scaled-up or full scale CO₂ sparge system is a feasible option





No groundwater extraction required, therefore, no wastewater generated

No ex situ treatment eliminating contact with equipment and piping materials

Pulsed operation could be an effective application to further reduce operating costs

A single technology would be applicable for both fresh and saline waters





QUESTIONS??

