



# Case Study: How to Avoid Failures in the Design and Installation of Permeable Reactive Barriers

RemTech – Banff, AB

October 11, 2018

John Clarke and Kevin French



# Presenters

## Kevin French, P.Eng

- Vice President, Vertex Environmental Inc.
- B.A.Sc., Civil/Environmental Engineering, University of Waterloo
- 30+ years environmental engineering; 25 in consulting and 5 as a remedial contractor



## John Clarke, P.Eng.

- Senior Project Manager, Milestone Environmental Contracting Inc.
- B.Sc. Hons., Earth Sciences, Memorial University of Newfoundland; B.Eng., Civil Engineering, McGill University
- 25+ years in environmental engineering, 21 as a remedial contractor

# Vertex Environmental Inc.



**In-Situ  
Remediation**




**Ex-Situ  
Remediation**




**High Resolution  
Characterization**



**Treatment  
Systems**



**Remedial  
Design**



**Bench-Scale  
Testing**



# Milestone Environmental Contracting Inc.

**Soil and Groundwater Remediation, Water Treatment**

**Passive Reactive Barrier Walls**

**Groundwater Cut-off Walls (soil-bentonite, cement, concrete)**

**Lagoon and Pond Remediation**

**Remedial Excavation with Shoring or Underpinning**

**Soil Stabilization**


***In-situ* Remediation**

**Landfill Closure and Capping, Mine Reclamation**

**Design-build Remediation / Contracting**




# Presentation Overview



- Permeable Reactive Barriers
- Site Background & Project Objective
- Overview of Site Conditions
- Bench-Scale Testing & Preliminary Design
- High-Resolution Site Characterization
- Updated Final Design
- Full-Scale Installation
- Quality Assurance / Quality Control
- Performance Monitoring
- Lessons Learned
- Questions

# Permeable Reactive Barriers (PRBs)

# Permeable Reactive Barriers (PRBs)



- PRBs intercept and treat contaminated groundwater plumes (passive)
- Allow groundwater to flow through unimpeded
- Different reactive media for different contaminants
- Original zero-valent iron (ZVI) PRBs ("Iron Walls") installed in mid-1990 still functional
- Can be dug or injected
- Sustainable (no energy use to operate)

# Site Background & Project Objective



# Site Background & Project Objective

- Municipal client tendered a competitive bid contract for a “Pump & Treat” system to hydraulically contain contaminated groundwater plume from suspected off-site spill of PCE
- Milestone offered an alternative design to install a PRB that would achieve similar results and significantly reduce future operation and maintenance costs for the municipality
- Milestone and Vertex teamed to provide proof-of-concept for alternative design to the municipality and then to design and install the PRB
- Remedial objective was to prevent the plume of contaminated groundwater from continuing to migrate across the site by reducing CVOC concentrations to below PSS levels

# Overview of Site Conditions

# Overview of Site Conditions

- Contamination initially identified by former property owner in 1998
- Municipality purchased the site 2008
- Converted into a parking lot / farmers market
- Main groundwater contaminants were volatile organic compounds (VOCs); primarily tetrachloroethylene (PCE) and its degradation products
- No DNAPL suspected to be present at the site (i.e., off-site source)
- Main pathway of concern was via groundwater flow through the overburden soils

# Overview of Site Conditions

- Geology:
  - Sand and gravel fill with occasional cobbles and organic matter
  - Native soil consisting of sand, silty sand and silty clay till
  - Some reported “flowing” sands
  - Clay till served as “confining layer”
  - Limestone / dolostone bedrock
  - Soil thicknesses were approximately 6 to 7 mbgs
- Hydrogeology:
  - Water levels in the overburden at approx. 2.4 to 3.4 mbgs
  - Horizontal hydraulic gradient of approx. 0.03 to 0.06
  - Hydraulic conductivity of approx.  $1.2\text{E-}07$  to  $3.5\text{E-}04$  m/s
  - Estimated groundwater flow velocity of 40 m/yr



# Overview of Site Conditions



# Groundwater Elevation Contours and Flow

The map displays groundwater elevation contours and flow directions. Key features include:

- Monitoring Wells (MW) and Boreholes (BH):** Labeled with their IDs and elevations.
  - MW115: 96.02
  - MW05-5: 96.61
  - MW118: 96.35
  - MW119: 96.40
  - MW112: 96.50
  - MW108: 96.53
  - MW111: 92.67
  - BH/MW-09-16: 96.61
  - BH/MW-09-7: 96.53
  - BH/MW-08-19: 96.24
  - BH/MW-08-6: 96.35
  - MW102: 96.41
  - BH/MW-08-5: 96.48
  - BH/MW-08-4: 96.51
  - BH/MW-09-8: 96.55
  - BH/MW-09-12: 96.53
  - BH/MW-08-3: 96.64
  - BH/MW-09-14: 97.12
  - BH/MW-08-1: 96.16
  - BH/MW-08-16: 96.41
- Groundwater Elevation Contours:** Blue lines showing the groundwater elevation profile.
- Flow Direction:** Indicated by black arrows, showing flow generally towards the right and slightly upwards.
- Street:** Labeled on the left side of the map.

**Milestone ENVIRONMENTAL CONTRACTING INC.**


**VERTEX**





# Overview of Site Conditions

## Geologic Cross-Section



PROPERTY LINE

GROUNDWATER LINE

WATER LEVEL MEASURED

(A)

(B)

SAND & GRAVEL FILL (MIXED WITH OCCASIONAL DEBRIS)

BOULDER FILL WITH SAND & GRAVEL

(C)

(D)

(E)

(F)

ORGANIC FILL (MIXED WITH SOIL & OCCASIONAL DEBRIS)

NATIVE SILT/CLAY WITH SAND

NATIVE SAND WITH SILT & CLAY & OCCASIONAL GRAVEL SEAMS

NATIVE SANDY CLAY TILL WITH GRAVEL & SILT

(G)


LIMESTONE BEDROCK

BOREHOLE

MONITORING WELL WITH SCREEN INTERVAL



# Overview of Site Conditions



# Preliminary Design & Bench-Scale Testing

# Preliminary Design

1a [- Get all site data  
Review horizontal, vertical, overtime

- review AMEC approach - design  
- variables

1b [- review ITRC other data - "

2 [- run our design  
→ Sensitivity Analysis

(Brochler Model)

3 [- what data do we need to  
collect to support assumptions?  
- K


4 Contingency - ZVI Injection  
up-gradient + at depth

- saturated thickness  
- vertical profile → VOBs needed  
→ VOBs & PWT


- saturated  
- K → measured  
→ assumed  
→ non-site test  
→ slug  
→ pumping in  
→ HPT or

Assessment of Phase 2

- Source - time  
- Velocity




# Preliminary Design





# Preliminary Design




# Bench-Scale Testing

- The municipal client did not have direct experience with the ZVI PRB technology
- Bench-scale treatability testing was offered to provide the needed “proof-of-concept” and assurances to client
- Samples of contaminated groundwater obtained from the site and mixed with combinations of ZVI (10%, 20% & 30%) and sand



# Bench-Scale Testing



- Parameter-specific degradation half-lives calculated based on information obtained from bench-scale tests
- Compared to literature references as a reality check
- >95% reduction in total CVOCs achieved over 22 days of testing


# Preliminary Design & Bench-Scale Testing

- Preliminary PRB design was determined using a computer model that assessed:
  - CVOOC concentrations in groundwater and target treatment concentrations
  - Physical, geological and hydrogeological conditions of the soils at the site and in the planned PRB
  - CVOOC half-lives from the bench-scale testing (first order decay)
  - Groundwater temperature conditions for site
  - Groundwater flux balance through “funnel & gate” PRB configuration
- In order to meet PSS levels using reported groundwater flow velocities a PRB 1.0 m thick would need to contain 37% ZVI




# Preliminary Design & Bench-Scale Testing

- Sensitivity analysis completed on all input variables
- Model (and therefore results) most sensitive to hydraulic conductivity
- k-values varied by over 3 orders of magnitude, other parameters by  $<1$
- Recommended additional site characterization to reduce uncertainty in predicted results



# High-Resolution Site Characterization


# High-Resolution Site Characterization



## Hydraulic Profiling Tool (HPT)

- Direct-push
- Assess formation permeability
- Water injected into the ground; flow and back-pressure measured
- EC: Estimate of soil type
- Identifies location of water table (no wells)
- Result: Empirical estimate of hydraulic conductivity on a cm scale
- HPT deployed at the site to find preferential flow paths in the saturated zone and to define lower “confining layer”

# High-Resolution Site Characterization





# High-Resolution Site Characterization






# High-Resolution Site Characterization






# HPT Case Study – HPT vs BH



# HPT Case Study – PRB Visualization



# Updated Final Design



# Updated Final Design

- Data from the HPT testing activities was used to update the preliminary design for the PRB:

Parameter	Preliminary Design	Final Design	Delta
SW Funnel Depth (m)	5.3	5.3 to 6.3	0.0 to +1.0
Gate Depth (m)	5.3	5.0 to 5.6	-0.3 to +0.3
N Funnel Depth (m)	5.3	5.0	-0.3
Thickness (m)	1.0	0.9	-0.1
Height (m)	3.3	3.1 to 3.7	-0.2 to +0.4
ZVI Concent (%)	37%	30%	-7%

- In order to meet PSS reduction using updated site data a PRB containing 30% ZVI would now only need to be 0.9 m thick (~27% savings)

# Full-Scale Installation

# Full-Scale Installation



- Cut and fill method PRB, with biopolymer slurry (in case of flowing sands)
- Completed over 6 days on-site
- ZVI mix for 12 m long PRB “Gate”: 22 tonnes ZVI, 51.2 tonnes coarse sand
- Concrete wing walls for “Funnel” were 12 m long and 6 m long



# Full-Scale Installation



- Strip asphalt
- Cut / fill (using trench box) the “Funnel” wing walls with concrete
- Excavate PRB “Gate” section using biopolymer slurry (on-site tank: 30,000 liters water, 300 kg of guar gum) for sidewall support
- Coarse sand for PRB “Gate” delivered in cement mixing truck
- ZVI added to truck and blended



# Full-Scale Installation



- Backfill PRB “Gate” section with ZVI / sand mixture and avoid gravity separation through slurry
- Break slurry and pump back from trench into on-site tank for off-site disposal (approx. 9,000 liters)
- Place and compact granular trench cap
- Restore surface asphalt
- Remove excavation spoils from site

# Full-Scale Installation





# Full-Scale Installation





# Full-Scale Installation





# Full-Scale Installation



# Quality Assurance / Quality Control

# Quality Assurance / Quality Control

- Samples of ZVI / sand mixture collected from each batch mixed on-site and subjected to magnetic separation testing
- Post-installation boreholes drilled through “Gate” portion of PRB and subjected to magnetic separation testing (similar results)
- One monitoring well drilled approx. 1.5 m downgradient of PRB for groundwater sampling and analysis


Date	Batch	ZVI (%)
26/04/2016	1	32.3%
26/04/2016	2	31.9%
26/04/2016	3	31.5%
28/04/2016	4	33.7%
28/04/2016	5	34.2%
Average		32.7%

Target ZVI Concentration = 30%


# Performance Monitoring



# Quality Assurance / Quality Control



# Performance Monitoring



**Generic Standards Met!**

# Lessons Learned

# Lessons Learned



- Thoroughly review and validate existing ESA data
- Develop a CSM and preliminary design
- Complete a sensitivity analysis
- Identify any significant data gaps that result in unacceptable uncertainty
- Collect additional site data, if needed, to resolve uncertainty
- Complete bench-scale testing, if needed, to assess site-specific response
- Refine design to tolerable certainty / safety factor



# Lessons Learned (cont'd)



- Ensure that field installation is as per design
- Implement a robust QA/QC programme as confirmation
- Large boulder / debris along trench alignment can cause trench to widen: have additional admixture material on-site to accommodate
- Allow ZVI / sand admixture to set / settle prior to placement of granular cap: top up as required
- Ensure on-going communication between contractor and consultant during installation to ensure any design modifications needed to accommodate field conditions are undertaken with overall design context / goal in mind

## Lessons Learned (cont'd)



- **Start with a qualified team of consultants & contractors**
- **Communication is key between entire project team**
- ***Have fun and slay dragons!!!!***





# Questions?

## Thank You for Your Time

**Kevin French**

Vertex Environmental Inc.  
(519) 653-8444 x 303  
(519) 404-5442 mobile  
kevinf@vertexenvironmental.ca

[www.vertexenvironmental.ca](http://www.vertexenvironmental.ca)

**John Clarke**

Milestone Environmental Contracting Inc.  
(604) 283-9292  
(604) 240-5952 mobile  
johnc@milestoneenv.ca

[www.milestoneenv.ca](http://www.milestoneenv.ca)

**Milestone**  
ENVIRONMENTAL CONTRACTING INC.

